

Date: Wednesday, 1/18/2006 4:04:48 PM
 User: Kim Johnston

Process Sheet

Customer : CU-DAR001 Dart Helicopters Services	Drawing Name : BRACKET ASSEMBLY
Job Number : 25556C	
Estimate Number : 10280	
P.O. Number : N/A	Part Number : D3137043
This Issue : 1/18/2006 S.O. No. : N/A	Drawing Number : D3137 REV E
Prsht Rev. : NC	Project Number : N/A
First Issue : N/A Type : MACHINED PARTS	Drawing Revision : E
Previous Run : 25457	Material : N/A
Written By : <u>SEE COMMENT BELOW</u>	Due Date : 2/15/2006 Qty: 4 Um: Each
Checked & Approved By : <u>SEE ABOVE DATE & USER</u>	
Comment : Est Rev:A 04.02.18 New issue KJ/DS	

Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
----------------	------------------------------	----------------------

1.0	M174B0500X02000	17-4 SS Bar
-----	-----------------	-------------



Comment: Qty.: 0.4875 f(s)/Unit Total : 1.9501 f(s)
 Material: 17-4 SS Bar per AMS 5604/5643
 (M17-4-B0.500x02.000)
 Identify for D3137-7
 Batch: M19572

J.L 06.02.18 4

2.0	BAND SAW	BAND SAW
-----	----------	----------



Comment: BAND SAW .500
 Cut blanks: (1.000" x 2.000") 5.570" long

J.L 06.02.20 4

3.0	HAAS1	HAAS CNC VERTICAL MACHINING #1
-----	-------	--------------------------------



Comment: HAAS CNC VERTICAL MACHINING #1

1-Machine D3137-7 as per Folio FA3308 and Dwg D3137 Identify as D3137-7

2-Deburr

3-Scribe batch number

J.L 06.02.20 4

4.0	QC2	INSPECT PARTS AS THEY COME OFF MACHINE
-----	-----	--



Comment: INSPECT PARTS AS THEY COME OFF MACHINE

J.L 06.02.20 4

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date: Wednesday, 1/18/2006 4:04:48 PM
User: Kim Johnston

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: BRACKET ASSEMBLY

Job Number: 25556C

Part Number: D3137043

Job Number:



Seq. #:

Machine Or Operation:

Description :

5.0

QC8

SECOND CHECK



Comment: SECOND CHECK

M8 06/02/20

4

6.0

D31373

Guide



Comment: Qty.: 1.0000 Each(s)/Unit Total : 4.0000 Each(s)

Pick:

Qty Part Number

Description Batch

1 D3137-3

GUIDE

BAS012

M8 06/02/20

4

7.0

D31375

Washer



Comment: Qty.: 1.0000 Each(s)/Unit Total : 4.0000 Each(s)

Pick:

Qty Part Number

Description Batch

1 D3137-5

Washer

B24547

M8 06/02/20

4

8.0

MS24694S101

Screw



Comment: Qty.: 1.0000 Each(s)/Unit Total : 4.0000 Each(s)

Pick:

Qty Part Number

Description Batch

1 MS24694-s101

Screw

M16941

M8 06/02/20

4

9.0

SMALL FAB 1

SMALL & MEDIUM FAB RESOURCE 1



Comment: SMALL & MEDIUM FAB RESOURCE 1

Assemble D3137-043 as per Dwg D3137

M8 06/02/20

4

10.0

QC5

INSPECT WORK TO CURRENT STEP



Comment: INSPECT WORK TO CURRENT STEP

En 06/02/20

4

11.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and Stock

Location: _____

ST409

06/02/21 (4)

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes ☒ No ☐ DQA: PS Date: 06/02/22

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date: Wednesday, 1/18/2006 4:04:48 PM
User: Kim Johnston

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: BRACKET ASSEMBLY

Job Number: 25556C

Part Number: D3137043

Job Number:



Seq. #:

Machine Or Operation:

Description :

12.0

DC

DOCUMENT CONTROL



Comment: DOCUMENT CONTROL

Inspection Level 21

545 06/02/22 (4) PD 06/02/22 (4)

Job Completion



W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

DART AEROSPACE LTD		Work Order: 25556C
Description: Bracket		Part Number: D3137-7
Inspection Dwg: D3137	Rev: C2	Page 1 of 1

FIRST ARTICLE INSPECTION CHECKLIST

☒ First Article ☐ Prototype

Drawing Dimension	Tolerance	Actual Dimension	Accept	Reject	Method of Inspection	Comments
0.435	+/-0.010					
0.615	+/-0.010					
0.200	+/-0.010					
0.380	+/-0.010					
0.262	+/-0.010					
Ø0.500	+0.005/-0.000					
0.79	+/-0.030					
2.79	+/-0.030					
Ø0.560	+0.005/-0.000					
0.595	+/-0.010					
0.950	+/-0.010					
0.605	+/-0.010					
1.880	+/-0.010					
2.48	+/-0.030					
4.975	+/-0.010					
5.41	+/-0.030					
0.032	+/-0.010					
0.063	+/-0.010					
R0.062	+/-0.010					
0.162	+/-0.010					

Measured by: JL	Audited by:	Prototype Approval: N/A
Date: 06.02.20	Date:	Date: N/A


Rev	Date	Change	Revised by	Approved
A	03.11.12	New Issue P/O D3137-043	KJ/RF	
B	04.06.15	Changed & added dimensions	KJ/JLM	



DESIGN DS	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED #	APPROVED #	DRAWING NO. D3137	REV. E SHEET 1 OF 5
DATE 05.11.23		TITLE BRACKET ASSEMBLY	SCALE 1:1
A	02.04.17	NEW ISSUE	
B	03.01.16	ADD RIDGES; ADD MAT'L PROP.	
C	03.08.15	ADD -043	
D	04.11.03	RE-DESIGN D3137-5; CHANGE DIMS	
E	05.11.23	ADD -045	

RELEASED

05.12.09



D3137-041 BRACKET ASSEMBLY (SHOWN)
D3137-043 BRACKET ASSEMBLY (SIMILAR)
D3137-045 BRACKET ASSEMBLY (SIMILAR)


SHOP COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY
SUBJECT TO ELEMENT
WITHOUT NOTICE
WORK ORDER
NO. 25556C

Copyright © 2002 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

DART

DESIGN DS	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED #	APPROVED #	DRAWING NO. D3137	REV. E SHEET 2 OF 5
DATE 05.11.23	TITLE BRACKET ASSEMBLY		SCALE 1:1

**D3137-1 BRACKET:**

- 1) REPLACES PREMIER P/N B30-23000-105/-106 BRACKETS
- 2) MATERIAL: 17-4PH STAINLESS STEEL
PER AMS 5604 OR 5643 (REF DART SPEC. M17-4-B)
MIN ULTIMATE TENSILE = 150 ksi
MIN YIELD TENSILE = 100 ksi
- 3) FINISH: NONE
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) ALL DIMENSIONS ARE IN INCHES
- 6) BREAK ALL SHARP EDGES 0.005 TO 0.015
- 7) ENGRAVE DART LOGO USING 0.20 & P/N USING 0.15 LETTERS TO MAX. DEPTH 0.010
WITH A LOGO MIN TOOL RAD OF 0.093 & P/N MIN TOOL RAD 0.04 AS SHOWN
- 8) IDENTIFY WITH DART B/N USING FINE POINT PERMANENT INK MARKER

SEE DETAIL C

RELEASED
10/2/09
SHOP
REPORT
ENGINEERING

UNCONTROLLED COPY


Copyright © 2002 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.


WORK ORDER
NO. 25556 C

DART

DESIGN DS	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. D3137	REV. E SHEET 3 OF 5
DATE 05.11.23	TITLE BRACKET ASSEMBLY		SCALE 1:1

**D3137-3 GUIDE**

- 1) REPLACES PREMIER P/N B30-23000-207
- 2) MATERIAL: DELRIN BAR (REF DART SPEC. M-DELRIN-B)
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL EDGES 0.005 TO 0.015

**D3137-5 WASHER**

- 1) REPLACES PREMIER P/N B30-23000-209
- 2) MATERIAL: 6061-T6 (QQ-A-225/8 OR QQ-A-200/8) BAR (REF DART SPEC. M6061T6R)
- 3) FINISH: CHEMICAL CONVERSION COAT PER DART QSI 005 4.1
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) ALL DIMENSIONS ARE IN INCHES
- 6) BREAK ALL EDGES 0.005 TO 0.015

SHOP COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY
SUBJECT TO


Copyright © 2002 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

NO. 25556C

DART

DESIGN DS	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. D3137	REV. E SHEET 4 OF 5
DATE 05.11.23	TITLE BRACKET ASSEMBLY		SCALE 2:3

**D3137-7 BRACKET:**

- 1) MATERIAL: 17-4PH STAINLESS STEEL PER AMS 5604 OR 5643 (REF DART SPEC. M17-4-B)
MIN ULTIMATE TENSILE = 150 ksi
MIN YIELD TENSILE = 100 ksi
- 2) FINISH: NONE
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL SHARP EDGES 0.005 TO 0.015
- 6) ENGRAVE DART LOGO USING 0.20 & P/N USING 0.15 LETTERS TO MAX. DEPTH 0.010
WITH A LOGO MIN TOOL RAD OF 0.093 & P/N MIN TOOL RAD 0.04 AS SHOWN
- 7) IDENTIFY WITH DART B/N USING FINE POINT PERMANENT INK MARKER

Copyright © 2002 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

RELEASED

05.12.09

SHOWN
RETURNED
ENGINEER

UNCONTROLLED

SUBJECT


WITH HOLDING

WORK ORDER


NO. 25556 C

DART


DESIGN DS	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. D3137	REV. E SHEET 5 OF 5
DATE 05.11.23	TITLE BRACKET ASSEMBLY		SCALE 1:2





DETAIL C
RIDGE DETAIL
SCALE 1:20



DETAIL A
SCALE 1:1



DETAIL B
SCALE 1:1



E

D3137-2 BRACKET:

- 1) REPLACES PREMIER P/N B30-23000-105/-106 BRACKETS
- 2) MATERIAL: 17-4PH STAINLESS STEEL
PER AMS 5604 OR 5643 (REF DART SPEC. M17-4-B)
MIN ULTIMATE TENSILE = 150 ksi
MIN YIELD TENSILE = 100 ksi
- 3) FINISH: NONE
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) ALL DIMENSIONS ARE IN INCHES
- 6) BREAK ALL SHARP EDGES 0.005 TO 0.015
- 7) ENGRAVE DART LOGO USING 0.20 & P/N USING 0.15 LETTERS TO MAX. DEPTH 0.010
WITH A LOGO MIN TOOL RAD OF 0.093 & P/N MIN TOOL RAD 0.04 AS SHOWN
- 8) IDENTIFY WITH DART B/N USING FINE POINT PERMANENT INK MARKER

RELEASED

05.12.09 *[Signature]*

SHOOT COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY

Copyright © 2002 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

WORK COPY
NO. 25566C